

Pervious Concrete Costs

1. Excavate and export additional 391 cu.yds.	4,629.00
2. Provide and install geotextile fabric	2,300.00
3. Provide and Place 876 ton #57 gravel	20,503.00
4. Provide and Place 300 cu.yds. Pervious Concrete	60,769.00
5. Provide and Install wet curing blankets	3,000.00
Total	91,201.00

In this comparison, there would have been a \$22,244.00 COST SAVINGS if the project would have been constructed using a Pervious Concrete Stormwater System! That would have been close to 20% cost savings.